

Report No. FT-R1005

Testing of James Hardie NZ ExoTec façade panel top hat rainscreen façade system in accordance with AS/NZS 4284:2008 'Testing of building facades', plus extension.

Project: Generic ExoTec façade panel rainscreen system

Client: James Hardie NZ

Specifier: James Hardie NZ

Sample designer: James Hardie NZ

Manufacturer James Hardie NZ

Installer: Steve Cleary (Builder)

Test dates: 8-9 May 2017

Test Schedule The test order specified in AS/NZS 4284:2008 was followed, with preliminary testing on 8th May 2017 and the balance of the testing completed on 8th and 9th May 2017.

Persons present:

John Burgess, (IANZ authorised signatory), Singh Kamboj, (Technical manager, James Hardie NZ) and part time - Steve Cleary (SC Interiors), Josh Burg (Technical manager, JH Research Australia)

Test facility: Façade testing NZ Ltd,
127 Park Rd
Miramar
Wellington

IANZ accredited testing officer: John Burgess

IANZ accreditation number for testing 1259, including AS/NZS 4284.

Note: The "Test Request" has been attached as Appendix 10.2.

Tested by: John Burgess, IANZ Signatory

Checked by: Darryl Scott

This report may only be reproduced in full



Figure 1: Sample under construction for testing showing dry-side

1. Summary

The James Hardie NZ Exotec façade panel top hat rainscreen test sample was subjected to tests from the AS/NZS 4284:2008 testing suite, and had the following results.

1.1. Preliminary tests

Pass – air and water

1.1.1. Serviceability deflection test

Pass – studs showed minor deflections

1.2. Air infiltration test

Indeterminate at positive pressure (See discussion later)

Fail at negative pressure

1.3. Static Water penetration test

Pass – at 1050 Pa

1.4. Cyclic water penetration test

Pass – at between 525 and 2,100 Pa

1.5. Ultimate limit state pressure test

Pass – at +5.0 kPa and -5.0 kPa

2. Contents

1. Summary	2
1.1. Preliminary tests	2
1.1.1. Serviceability deflection test.....	2
1.2. Air infiltration test	2
1.3. Static Water penetration test.....	2
1.4. Cyclic water penetration test	2
1.5. Ultimate limit state pressure test	2
2. Contents	3
3. Figures.....	4
4. Tables.....	5
5. Notation	7
6. Apparatus	7
7. Sample	7
7.1. Orientation	7
7.2. Sample Description.....	7
7.3. Modifications to the sample.....	8
7.3.1. Modifications During Preliminary Testing	9
7.3.2. Modifications During AS/NZS 4284:2008 Testing	9
7.3.3. Modifications following AS/NZS 4284:2008 Testing	9
8. Procedure	9
8.1. Test Sequence.....	9
8.2. Preliminary Tests	9
8.2.1. Smoke Test	9
8.2.2. Static Pressure	9
8.2.3. Water	9
8.3. Structural test at serviceability limit state (SLS).....	10
8.3.1. Structural test pressures	10
8.3.2. Location of the displacement transducers	10
8.3.3. Pressure loading sequence.....	12
8.4. Air Infiltration.....	12
8.5. Water Penetration by Static pressure.....	12
8.6. Water penetration test by cyclic pressure.....	12
8.7. BMU restraint test	13
8.8. Structural test at ultimate limit state (ULS)	13
8.9. Seismic test	13
9. Results.....	14

9.1.	Preliminary water tests (AS/NZS 4284:2008 Part a).....	14
9.2.	Structural test at serviceability limit state (SLS) (AS/NZS 4284:2008 Part b).....	14
9.3.	Air infiltration (AS/NZS 4284:2008 Part c)	16
9.4.	Water penetration (AS/NZS 4284:2008 Part d)	16
9.4.1.	Static pressure water penetration.....	16
9.4.2.	Cyclic pressure water penetration	17
9.5.	Seismic test at serviceability limit displacement (AS/NZS 4284:2008 Part e)	17
9.6.	BMU restraint test	18
9.7.	Structural test at ultimate limit state air pressure (AS/NZS 4284:2008 Part g).....	18
9.8.	Ultimate limit state seismic test (AS/NZS 4284:2008 Part h)	18
10.	Appendices	20
10.1.	Serviceability deflections	20
10.2.	Test Request.....	22
10.3.	Drawings	24
10.4.	Further testing	28

3. Figures

Figure 1:	Sample under construction for testing showing dry-side.....	2
Figure 2:	RH Top of sample from wet side	5
Figure 3:	Lower LHS of sample from wet side	6
Figure 4:	LH Top of sample from wet side, under construction	6
Figure 5:	Lower RHS of sample from wet side	7
Figure 6:	Top hat sections on wet side of cladding, with cladding removed and holes in RAB board during disassembly.	8
Figure 7:	Water sprays on during static water test.....	10
Figure 8:	Location of displacement transducers on studs 1 and 2	11
Figure 9:	Photos of displacement transducers on stud beside window (Stud 1)	12
Figure 10:	Photos of transducers on stud in field of wall (Stud 2)	12
Figure 11:	Top right hand corner of sample connected to the seismic ram via steel plates and bolts through the framing.....	13
Figure 12:	Crack in RAB board following ULS seismic testing on system.....	19
Figure 13:	Displacements of transducers	20
Figure 14:	Zero table results from transducers	21
Figure 15:	Test request form – annotated and agreed.....	23
Figure 16:	Sketch of water leak locations during the extended E2/VM1 'WeatherPLus' test.....	28
Figure 17:	View from wet side of RAB board after removal of cladding, showing holes made in RAB board, and the damp patch from water seeping through the crack emanating from the head flashing.	29

4. Tables

Table 1: Preliminary static water test.....	14
Table 2: Preliminary cyclic water test pressures.....	14
Table 3: Summary of maximum transducer deflections in serviceability limit state testing ...	14
Table 4: Deflections of studs and deflection/span results for transducers.....	15
Table 5: Air tightness leakage results.....	16
Table 6 Static water leakage results.....	16
Table 7: Cyclic water test results.....	17
Table 8: Parameters for seismic deflections.....	17
Table 9: Post SLS seismic test water test pressures	17
Table 10: Ultimate limit state air pressure results	18
Table 11: Ultimate limit state seismic test parameters.....	18



Figure 2: RH Top of sample from wet side



Figure 3: Lower LHS of sample from wet side



Figure 4: LH Top of sample from wet side, under construction



Figure 5: Lower RHS of sample from wet side

5. Notation

The reference numbers from the AS/NZS 4284:2008 'Testing of building facades' document are used in the following from this point onwards, for ease of reference.

6. Apparatus

The James Hardie ExoTec Top Hat Rainscreen Façade system was tested using the FTNZ test facility.

7. Sample

7.1. Orientation

The orientation of all elements is typically recorded in this report as viewed from the outside of the test booth (dry side), being the inside of the façade when constructed. The inside of the test booth has the outside (wet side) of the façade.

7.2. Sample Description

The test arrangement consisted of a single storey test sample comprising the ExoTec façade panel system. The sample was approximately 3500 mm high and 4400 mm wide. The system was built on a 140 x 45 mm SG8 timber stud frame at 400 mm centres with nogs at 800 mm centres. A window of 765 x 1200mm, and a 600 x 400 mm return detail was included, clad in 6mm James Hardie RAB board, with 'Top Hat' metal rails fixed

vertically down the system between nog lines – not on the studs. A horizontal expansion joint was included at 2700 mm above the footer, including an Aluminium 'T' socket.

Differences between the drawings provided and the system as built included:

- the PVC "H" mould to the RAB board was overlaid with Protecto Superstick flashing tape to ensure airtightness of the test chamber.
- The ExoTec Top Hat base mould was used at the footer, with WANZ support bar and head flashing used at the window opening.




Figure 6: Top hat sections on wet side of cladding, with cladding removed and holes in RAB board during disassembly.

7.3. Modifications to the sample

Modification to the details were noted during testing, and changes were made to the drawings, as shown in the Appendix, and include:

- Foundation (Detail A)
- Vertical joint (Detail B)
- Internal corner (Detail C)
- External corner (Detail D)
- Window (head, jamb and sill) details (Details E, F, G)
- Horizontal joint (Detail H))

7.3.1. Modifications During Preliminary Testing

During preliminary cyclic water testing at 750 Pa a significant volume of water was seen on the dry side of the RAB board, leaking from the horizontal joint at the top of the sample. This was fixed with a batten and tape, and by adding a section of plywood ceiling to cover the top of the 'return' section of the cladding.

7.3.2. Modifications During AS/NZS 4284:2008 Testing

During the negative SLS deflection test, a batten holding the flexible butyl rubber at the foot, blew off when testing at -3500 Pa. This was replaced with a new section of batten and several screws, and testing resumed.

7.3.3. Modifications following AS/NZS 4284:2008 Testing

Holes were punched in the RAB board to establish an air pressure across the cladding, to allow a modification of the wetwall test of the E2/VM1 testing to be undertaken.

8. Procedure

Note: the same clause numbers have been used as in AS/NZS 4284 for ease of reference in the below.

8.1. Test Sequence

The tests were performed using the testing procedures of AS/NZS 4284:2008 in the cladding test facilities of Façade Testing NZ Ltd (FTNZ), Park Rd, Miramar, Wellington.

8.2. Preliminary Tests

The tests in clauses 8.2.2, 8.2.3 and 8.2.4 were conducted before the structural test.

8.2.1. Smoke Test

A smoke machine was used to identify air leakage sources in the sample following completion of the RAB board but prior to installation of ExoTec façade panel system. Where identified, air leakage sources were sealed prior to completion of the cladding erection.

8.2.2. Static Pressure

The client agreed to undertake the preliminary tests with a reduced SLS of 2 kPa for initial pressure, 750 Pa (0.3 x 2.5 kPa for static water), and then use the intended SLS of 3.5 kPa for standard testing. The test sample was subjected to the positive and negative SLS design wind pressures for 10 seconds. Air pressures of +2.1 kPa and -2.0 kPa were applied to the test sample. See Figure 7.

8.2.3. Water

Preliminary water tests were conducted under static and cyclic pressures, as per clauses 8.5 and 8.6. Air pressures were 750 Pa for static water testing, and were 750, 1000 and 1500 for the cyclic water testing.



Figure 7: Water sprays on during static water test


8.3. Structural test at serviceability limit state (SLS)

8.3.1. Structural test pressures

Following preliminary testing which used an SLS of 2000 Pa, the SLS test pressures of ± 3.5 kPa were used, although the first set pressure used was 3.0 kPa, not 3.5 kPa.

8.3.2. Location of the displacement transducers

Following agreement with the client, six displacement transducers were set to record deflection of the two studs that were expected to give the largest deflections - beside the window on the LHS, and in the free wall on the RHS, as shown in Figure 8.



Exotec Facade Panel
NZS2484 Test

Framing Layout

May 2017
www.jameshardie.co.nz

Figure 8: Location of displacement transducers on studs 1 and 2



Figure 9: Photos of displacement transducers on stud beside window (Stud 1)



Figure 10: Photos of transducers on stud in field of wall (Stud 2)

8.3.3. Pressure loading sequence

The pressure loading sequence, (as per AS/NZS 4284) was requested by the client as ramping up in five steps, being 20%, 40%, 60%, 80% and 100%, before continuing with the ramp down, and negative pressures, as in Fig 1 of AS/NZS 4284: 2008.

8.4. Air Infiltration

The air infiltration test pressure of +/- 150 Pa was used. The test process involved measuring the sum of the booth leakage and the sample together.

8.5. Water Penetration by Static pressure

The water penetration test pressure of 1050 Pa was nominated by the specifier.

8.6. Water penetration test by cyclic pressure

The three stages of cyclic water penetration were nominated as follows:

Stage 1: 525 - 1050 Pa

Stage 2: 700 – 1400 Pa

Stage 3: 1050 – 2100 Pa

8.7. BMU restraint test

A BMU restraint test was not requested as part of the AS/NZS 4284:2008 test procedure.

8.8. Structural test at ultimate limit state (ULS)

The test pressures of +5.0 kPa, and -5.0 kPa were applied to the sample.

8.9. Seismic test

Seismic displacement values of ± 18 mm for SLS and ± 30 mm ULS were agreed with the client.



Figure 11: Top right hand corner of sample connected to the seismic ram via steel plates and bolts through the framing.

9. Results

9.1. Preliminary water tests (AS/NZS 4284:2008 Part a)

The performance requirements below, are as per the request of the client.

Preliminary static water test			
Stage	Air pressure (Pa)	Duration	Result
	0	5 minutes	No water leaks
1	750	15 minutes	No water leaks
2	0	5 minutes	No water leaks

Table 1: Preliminary static water test

Preliminary cyclic water test			
Phase	Air pressure (Pa)	Duration	Result
	0	5 minutes	No water leaks
1	375-750	5 minutes	No water leaks
2	500-1000	5 minutes	No water leaks
3	750-1500	5 minutes	No water leaks

Table 2: Preliminary cyclic water test pressures

9.2. Structural test at serviceability limit state (SLS) (AS/NZS 4284:2008 Part b)

Displacement at transducer				
Transducer Number	Transducer Location	Span (mm)	Max pos displacement (mm)	Max neg displacement (mm)
1	Stud 1 top	3510	9.43	-12.21
2	Stud 1 mid	3510	21.24	-21.26
3	Stud 1 lower	3510	28.62	-20.48
4	Stud 2 top	3510	6.79	-8.29
5	Stud 2 mid	3510	6.87	-8.27
6	Stud 2 lower	3510	13.38	-17.72

Table 3: Summary of maximum transducer deflections in serviceability limit state testing

The gross deflections of the studs at each of the locations shown in Figure 8, and the photos (Figure 9 and Figure 10) are summarised in Table 3, (maximum values shown), with net deflections of the members shown in Table 4. The gross individual transducer readings for all transducers and zero table are in the Appendix.

Note: The two values of N/A in Table 4 are due to transducer two running out of travel, which was discovered after the conclusion of the testing.

Transducer 2 was re-set during testing. See the Appendix for explanation.

Deflection of studs				
	Stud #1		Stud #2	
Pressure (Pa)	Net Deflection (mm)	Defl/Span	Net Deflection (mm)	Defl/Span
0	0.00	0.0000	0.00	0.0000
3000	10.51	0.0033	6.19	0.0020
0	0.09	0.0000	-0.01	0.0000
700	2.19	0.0007	1.24	0.0004
1400	4.70	0.0015	2.68	0.0009
2100	7.51	0.0024	4.34	0.0014
2800	10.10	0.0032	5.92	0.0019
3500	13.18	0.0042	7.73	0.0025
0	0.06	0.0000	0.03	0.0000
3500	13.28	0.0042	7.79	0.0025
2800	11.39	0.0036	6.59	0.0021
2100	9.12	0.0029	5.18	0.0016
1400	6.38	0.0020	3.64	0.0012
700	3.31	0.0011	1.89	0.0006
0	0.16	0.0001	0.11	0.0000
-3500	N/A	N/A	-10.94	-0.0035
0	-3.00	-0.0010	-2.40	-0.0008
-700	-5.63	-0.0018	-4.01	-0.0013
-1400	-8.15	-0.0026	-5.57	-0.0018
-2100	-11.03	-0.0035	-7.41	-0.0024
-2800	N/A	N/A	-9.23	-0.0029
-3500	-15.49	-0.0049	-11.14	-0.0035
0	-3.00	-0.0010	-2.66	-0.0008
-3500	-15.53	-0.0049	-11.17	-0.0036
-2800	-13.36	-0.0043	-9.93	-0.0032
-2100	-11.05	-0.0035	-8.54	-0.0027
-1400	-8.31	-0.0026	-6.87	-0.0022
-700	-5.24	-0.0017	-4.90	-0.0016
0	-2.87	-0.0009	-2.75	-0.0009
3500	15.21	0.0048	12.05	0.0038
0	0.81	0.0003	-0.32	-0.0001

Table 4: Deflections of studs and deflection/span results for transducers

9.3. Air infiltration (AS/NZS 4284:2008 Part c)

This test was undertaken to determine the airtightness of the sample.

The airtightness of interest was the cladding.

Overall area: 18.4 m²
 Allowable leakage, at 1.6 l/m².s 29.4 l/s

Airtightness measurements @ 150 Pa ΔP		
	Positive pressure (infiltration) l/s	Negative pressure (exfiltration) l/s
Measured (booth + sample)	29.4 ± 0.6	33.5 ± 0.7
Calculated sample	< 29 l/s	< 34 l/s

Table 5: Air tightness leakage results

The airtightness of the 'sample plus booth' in the positive pressure scenario was within the experimental error of measurement. Therefore, a compliance statement cannot be made conclusively for air infiltration. While there was considerable air leaking around the perimeter of the sample, the airtightness of the system is largely dependent upon the airtightness of the RAB board. Hence, effort was not expended to find and seal these leaks, or to blank off the sample area to find the base leakage of the booth and perimeter seal.

The exfiltration of air from the sample under negative pressure exceeded the allowable leakage, but was not of concern as discussed above.

9.4. Water penetration (AS/NZS 4284:2008 Part d)

9.4.1. Static pressure water penetration

The results of the static water tests, as per clause 8.5 are shown below.

Static water test			
Stage	Air pressure (Pa)	Duration	Result
0	0	5 minutes	No water leaks
1	1050	15 minutes	No water leaks
2	0	5 minutes	No water leaks

Table 6 Static water leakage results

There were no water leaks, meeting the requirement of the standard.

9.4.2. Cyclic pressure water penetration

Cyclic water test			
Phase	Air pressure (Pa)	Duration	Result
	0	5 minutes	No water leaks
1	525 – 1050	5 minutes	No water leaks
2	700 – 1040	5 minutes	No water leaks
3	1050 – 2100	5 minutes	No water leaks

Table 7: Cyclic water test results

There were no water leaks, meeting the requirement of the standard.

9.5. Seismic test at serviceability limit displacement (AS/NZS 4284:2008 Part e)

The seismic displacement test from clause 8.9 of AS/NZS 4284 was performed. The test displacement was generated with the ram mounted at the top of the sample, in the plane of the façade. The displacement, d, number of cycles, n, and period, T, were as shown in Table 8.

The displacements were achieved using the seismic ram applying load to the top ribbon plate. Changes in the movement joint location and width were not recorded.

Seismic deflection parameters (SLS)			
Distance (d ± x mm)	Cycles (n)	Period (T, seconds)	Pause at mid-point and ends (sec)
18 ± 1 mm	10	10 mm/sec	10
20 ± 2 mm	10	10 mm/sec	10

Table 8: Parameters for seismic deflections

The seismic deflection testing at ±20 mm was undertaken straight after the SLS seismic deflection of ±18 mm, and resulted in a fine crack occurring at the head of the window. The cyclic water penetration test was performed following the seismic test with the results as follows.

Cyclic water test			
Phase	Air pressure (Pa)	Duration	Result
	0	5 minutes	No water leaks
1	525 – 1050	5 minutes	No water leaks
2	700 – 1040	5 minutes	No water leaks
3	1050 – 2100	5 minutes	Dampness on back of RAB board around crack in RAB board. No water leakage.

Table 9: Post SLS seismic test water test pressures

9.6. BMU restraint test

Not requested.

9.7. Structural test at ultimate limit state air pressure (AS/NZS 4284:2008 Part g)

Ultimate Limit State (ULS) air pressure test	
Air pressure (Pa)	Result
+5000	OK
- 5000	OK

Table 10: Ultimate limit state air pressure results

There was no permanent distortion or collapse during the ULS air pressure test.

9.8. Ultimate limit state seismic test (AS/NZS 4284:2008 Part h)

ULS seismic deflections			
Distance (\pm x mm)	Cycles (n)	Period (T, seconds)	Pause at ends (sec)
30 mm	10	Approx. 10 sec, with 3-4 sec between end points	10

Table 11: Ultimate limit state seismic test parameters

There was minor damage to the RAB board from the end of the window head flashing where the RAB board cracked for an approximate distance of 200 mm. See photo in Figure 12. This extended and widened the crack first noticed following the ± 20 mm seismic displacement.



Figure 12: Crack in RAB board following ULS seismic testing on system

Following the completion of the AS/NZS 4284 tests, further testing was undertaken as noted in the Appendix. This is outside the scope of the IANZ Accreditation, but provides information about the weathertightness of the cladding panels.

Prepared By:

John Burgess

IANZ-accredited test engineer

Checked By:

Darryl Scott

Manager Façade Testing NZ Ltd

10. Appendices

10.1. Serviceability deflections

Displacements								
	1	2a	2b	2 (Generated)	3	4	5	6
0	0	0	0	0	0	0	0	0
3000	7.52	16.8		16.8	5.06	5.41	10.6	3.42
0	0.18	0.27		0.27	0.18	0.2	0.16	0.13
700	1.64	3.56		3.56	1.11	1.16	2.18	0.73
1400	3.4	7.55		7.55	2.3	2.33	4.61	1.53
2100	5.57	12.14		12.14	3.7	3.95	7.57	2.51
2800	7.26	16.16		16.16	4.87	5.26	10.2	3.3
3500	9.22	21.02		21.02	6.46	6.83	13.28	4.28
0	0.12	0.26		0.26	0.29	0.27	0.24	0.15
3500	9.29	21.24		21.24	6.63	6.87	13.38	4.31
2800	8.29	18.44		18.44	5.82	6.07	11.51	3.77
2100	6.99	15.02		15.02	4.81	5.06	9.28	3.14
1400	5.21	10.78		10.78	3.59	3.54	6.55	2.29
700	3	5.86		5.86	2.11	2.19	3.63	1.3
0	0.28	0.54		0.54	0.48	0.39	0.43	0.25
-3500	-12.02	-21.26		-21.26	-8.04	-7.98	-17.24	-4.63
0	-3.28	-5.61	0.94	-5.61	-1.94	-2.43	-4.22	-1.21
-700	-5.78	-10.16		-10.16	-3.28	-3.64	-6.74	-1.83
-1400	-7.32	-14.01		-14.01	-4.41	-4.66	-9.1	-2.41
-2100	-8.98	-18.38		-18.38	-5.72	-5.82	-11.9	-3.17
-2800	-10.59	-21.21	-15.91	-21.21	-7	-7	-14.69	-3.93
-3500	-12.21		-20.41	-25.71	-8.24	-8.26	-17.68	-4.83
0	-3.49		-0.53	-5.83	-2.17	-2.65	-4.66	-1.35
-3500	-12.21		-20.48	-25.78	-8.29	-8.27	-17.72	-4.83
-2800	-11.18		-17.41	-22.71	-7.52	-7.43	-15.82	-4.35
-2100	-9.88		-13.96	-19.26	-6.55	-6.48	-13.65	-3.74
-1400	-8.31		-9.81	-15.11	-5.3	-5.33	-11.03	-2.99
-700	-6.53		-5.15	-10.45	-3.9	-4.13	-8.06	-2.2
0	-3.51		-0.42	-5.72	-2.2	-2.65	-4.75	-1.35
3500	9.43		28.62	23.32	6.79	6.82	13.34	-4.23
0	-0.27		6.02	0.72	0.09	-0.06	-0.4	-0.1
Max pos	9.43	21.24	28.62	23.32	6.79	6.87	13.38	4.31
Max neg	-12.21	-21.26	-20.48	-25.78	-8.29	-8.27	-17.72	-4.83

Figure 13: Displacements of transducers

Note: Transducer 2 left the surface of the stud during the negative pressure application at 3500 Pa. It is possible that the transducer was also beyond its range at -2800 Pa, so these values have been recorded here, but noted as 'not applicable' in the body of the report. The transducer was reset, and results recorded as 2b. The column marked "2 Generated" are the readings offset by the difference between the readings of transducer 2 before and after being re-set. Testing was continued from this point.

Zero table		
Zeroes	Stud 1	Stud 2
Z1	0.09	-0.01
Z2	0.06	0.03
Z3	0.16	0.11
Z4	-3.00	-2.40
Z5	-3.00	-2.66
Z6	-2.87	-2.75
Z7	0.81	-0.32

Figure 14: Zero table results from transducers

Successive member displacements can be seen in the Zero table above, and did not exceed the ± 3 mm allowed for structural framing members.

10.2. Test Request

**TEST REQUEST
FORM**

Project: Exotec Façade Panel Test-4284/2008

Client: James Hordie NZ

Specifier: —————

Sample designer/manufacturer: James Hordie NZ

Installer: Steve Cleary

Date(s) of test requested: Mid June 2017 or earlier

Test schedule required: (Cross out those Sections not required—a, b, c, d and g are mandatory to claim compliance with this Standard, AS/NZS 4284.)

<input checked="" type="checkbox"/> a—Preliminary	<input checked="" type="checkbox"/> b—Structural at SLS	<input checked="" type="checkbox"/> c—Air infiltration
<input checked="" type="checkbox"/> d—Water at static and cyclic	<input checked="" type="checkbox"/> e—Seismic at SLS with water	<input type="checkbox"/> f—BMU restraint test
<input checked="" type="checkbox"/> g—Strength at ULS	<input checked="" type="checkbox"/> h—Seismic at ULS	<input type="checkbox"/> i—Seal degradation

General description of test sample

Drawings of the test sample attached? ☒ Y/N

Certificate of Identification attached? Y/N

Information to be submitted a minimum of 48 hours prior to testing:

1. A set of scale drawings and specifications for the test sample showing:
 - a) An inside elevation.
 - b) Full sized or dimensioned cross sections through the facade with components suitably identified by material, die number or similar.
 - c) Position of any viewing panels for water testing
 - d) All significant dimensions.
 - e) Glass thickness, type and condition.
 - f) Gaskets, glazing methods, sash and joint sealing methods.
 - g) Sealant types used and their locations.
 - h) Hardware fitted (hinges, stays, catches etc.).
 - i) A number assigned to each panel and light whether opening or fixed where the quantity of lights makes it difficult to describe location.
 - j) A reference number or description for identification of the unit.

AS/NZS 4284:2008

20


SPECIFIC TEST REQUIREMENTS


Section	Test Name	Clause	Required parameters	
a	Preliminary test	8.2.1	1 kPa	SLS @ ± 2.5 kPa for prelim (0.75 kPa static water)
	SLS pressure	8.2.2/8.3	SLS(+) = 3.5 kPa SLS(-) = 3.5 kPa	
	Water static	8.2.3/8.5	Static water test pressure = 1.05 kPa	
	Water—Cyclic	8.2.3/8.6	Cyclic test pressure Stage 1 = 0.5 kPa	to 1 kPa
		8.2.3/8.6	Cyclic test pressure Stage 2 = 0.7 kPa	to 1.5 kPa
		8.2.3/8.6	Cyclic test pressure Stage 3 = 1.05 kPa	to 2.0 kPa
b	Structural test at SLS	8.3.2	Location of transducers noted on drawings? Y/N <i>See over</i>	
		8.3.3	Pressure steps?	
			Max. displacement? = 20 mm	
Members or panels		Deflection/span limit ratio		
ExoTEC PANEL		span/250		
TOP HAT SECTION		span/250		
c	Air infiltration test	Test pressure	(+) = 150 Pa (-) = 150 Pa	
		Air infiltration limit = 1.6 (l/m²s)		
d	Water test (static and cyclic)	Pressure (Pa)	Duration (mins)	Duration and spray intensity
	Static	750 Pa		15 min, 0.05 L/m² s
	Cyclic 1	As per 8.5.1 or (a) above		5 min, 0.05 L/m² s
	Cyclic 2			5 min, 0.05 L/m² s
	Cyclic 3			5 min, 0.05 L/m² s
Additional water penetration requirements?				
e	Seismic at SLS	(Water test repeated after)		
	Support beam movement allowed =	± 15 mm or ± 20 mm		
	Number of cycles =	10 cycles		
	Frequency of movement =			
f	BMU restraint	Test load across face of sample = kN		
		Test load perpendicular to sample = kN		
g	Strength at ULS	Test pressure	(+) = 5 kPa (-) = 5 kPa	
h	Seismic at ULS			
	Support beam movement allowed =	± 30 mm		
	Number of cycles =	10		
	Frequency of movement =	Hz		
i	Seal degradation	10% air seal removal? Y/N		
Describe seals to be altered <i>Window seals</i>				


COPYRIGHT

Figure 15: Test request form – annotated and agreed

10.3. Drawings








May 2017
www.jameshardie.co.nz

Construction Details

Exotec Facade Panel
NZS4284 Test





10.4. Further testing

Following the completion of the AS/NZS 4284 testing, holes were formed in each of the stud cavities through the RAB board. This was undertaken in an attempt to reduce the air pressure held by the RAB board to about half the air pressure drop across the sample. The hope was that about half the air pressure would be held across the cladding, and about half across the RAB board for this test.

BRANZ is currently developing the WeatherPlus test for mid-rise commercial buildings and proposing that the 50 Pa air pressure from the E2/VM1 test be raised to a 70 Pa air pressure test. Hence, the static "Wetwall" test from E2/VM1 was undertaken with a 150 Pa pressure difference across the system.

Results showed that the crack from the LHS of the window head flashing (at 1) allowed some seepage of water through the RAB board. Water seeped through the joint between the stud and the bottom plate at (2), and water splattered up from the footer flashing at points 3, 4 and 5.

Point 6 had water that was dripping down inside the metal top hat batten, coming out through the defect in the RAB board. This water was contained, and did not spatter on the back of the RAB board.

The test would have passed this section of the extended E2/VM1 'WeatherPlus' test, since all this water was managed appropriately.




Figure 16: Sketch of water leak locations during the extended E2/VM1 'WeatherPLUS' test.



Figure 17: View from wet side of RAB board after removal of cladding, showing holes made in RAB board, and the damp patch from water seeping through the crack emanating from the head flashing.